

# Holmes Run Trail Repair Project Community Meeting Update #2

May 24, 2022 at 6:30 p.m.

Department of Project Implementation
Department of Recreation, Parks & Cultural Activities





# Agenda

- Welcome & Introductions
- Project Background
  - Stantec Inc TEIR 1
  - Volkert Inc TEIR 2
- Budget & Schedule
- Planned Additional Trail Improvements
- Open Q & A
- How do I Stay Informed



# Welcome & Introductions

- Project Manager
  - Department of Project Implementation
    - Ayoub Hassen, Project Manager <u>Ayoub.Hassen@alexandriava.gov</u>
    - Daphne Kott, Project Director
       <u>Daphne.Kott@alexandriva.gov</u>
- Project Sponsor
  - Department of Recreation, Parks & Cultural Activities
    - Jack Browand, Deputy Director <u>Jack.Browand@alexandriava.gov</u>
    - Bethany Znidersic, Acting Division Chief Bethany.Znidersic@alexandriava.gov



# Welcome & Introductions

- Design consultant TEIR 1
  - Stantec Inc
    - Matt Martin, Project Manager
- Design consultant TEIR 2
  - Volkert Inc
    - Brian Graham, Project Manager



# Project Background

- Incidents Resulting in Trail Damage
  - In 2018, a portion of Holmes Run Trail within Dora Kelley Park that connects to North Morgan Street was closed due to flooding and severe erosion that undermined stability and integrity of the trail and boardwalk.
  - In 2019, the City received historic flooding, which severely damaged three additional sections of Holmes Run Trail, including two bridge structures.
- Project Scope
  - Repair and improve the damaged trail portions to ensure repairs are sustainable and not subject to damage by future flood events.





### **Your Team**



Matt Martin, PE Project Manager



George Rhodes III, PLA Lead – Stream Restoration



Jerome Means, PE, PLS Lead – Trail Design



Doug Li, PhD, PE Lead – Structures



Bryan Close, PE, CFM Lead – Hydrologic and Hydraulic Modeling



Megan McCollough, PE, CFM Lead – Stormwater Management

#### **Support Services:**

Louis Sozio, Rice Associates – Survey Katie Fordney, PE, Terracon – Geotechnical





# Project Background



4600 Duke & Jordan Streets



Morgan Street cul-de-sac



North Ripley Street



Dora Kelley Park



Pedestrian Bridge Replacement:
Holmes Run Trail over Tributary to Holmes
4600 Duke Street
Design consultant TEIR 2

### **Holmes Run Trail Pedestrian Bridge**


#### June 6, 2020

- Bridge previously closed due to severe stream bank erosion
- Designed slope repair/protection using Gabion Baskets
- Project awarded for construction Summer 2021









### **Holmes Run Trail Pedestrian Bridge**

#### August 14, 2021


- High water event caused the slope to completely fail
- Alternative 1 Stabilize existing slope and foundations
- Alternative 2 Replace existing foundation and stabilize slope
- Alternative 3 Replace with new bridge
- Alternatives 1 and 2:
  - High risk of collapse during design or construction
  - Not cost effective shorter service life
- Alternative 3:
  - Extended service life with new bridge
  - Wider structure that can support vehicle loads
  - Deeper foundations with slope protection to withstand future high-water events



### **Holmes Run Trail Pedestrian Bridge**

#### **Proposed Bridge**

- Prefabricated weathering steel truss
- 12-foot-wide reinforced concrete deck
- Supports 30,000 lb. vehicle loads
- 10-foot longer span with graded slopes
- Riprap slope protection



ABUTMENT B

ABUTME

GENERAL NOTES

SING LAYOUT GOOD STEEL TRUSS SING.

Vera and

BEGINNING OF BRIDGE BACK OF BACK WALL 5TA, 100-90,00 FAGE OF BACKWALL BTA, 100-91,00

**BRIDGE TYPICAL SECTION** 



# **Budget & Schedule**

- Design & Construction Funding
  - FY 2021 Capital Improvement Program
    - \$1,000,000 Design Services
    - \$5,000,000 Construction Services

### Schedule

- 4600 Duke & Jordan Streets Tier 1
  - Design Completion June 2022
  - Construction Solicitation & Award: July 2022 November 2022
  - Construction: November 2022 May 2023
- Remaining Portions Tier 2
  - Design Awarded (January 2022)
  - Design: January 2022 January 2023
  - Construction Solicitation & Award: January 2023 May 2023
  - Construction: Summer 2023 Spring 2024\*

<sup>\*</sup>Project implementation schedule will be determined in the design phase





- Dora Kelley & Holmes Run Trail Decking from Beauregard Completed
- Dora Kelley Park Trail Surface Repairs from Chambliss east) – Completed
- Surface Repairs Beatley Bridge: Ongoing anticipated completion May 27
- Holmes Run Trail Concrete Surface Repairs south of Duke Street to Eisenhower Avenue – scheduled for June 2022
- Holmes Run Trail Asphalt Surface Repairs from Holmes Run Parkway to Ripley crossing (southside) scheduled for June 2022



# **Questions & Answers**

# How can I be informed?

## **Project Website**

https://www.alexandriava.gov/113304

# Alexandria eNews

**RPCA General Information** 

### **Project List-Serve**

Sign-up Today

Email: <u>Jack.Browand@alexandriava.gov</u>